KRISHNARAJASAGARA DIVISION.

Notification dated 17th December 1934.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Krishnarajasagara Division, Krishnarajasagara, up to 4 P.M., on 13th January 1935, for shifting Galigekere village, Krishnarajanagar Taluk. An approximate estimate of quantities is given below. These quantities are not guarateed :—

1. The plans may be seen at the Executive Engineer's Office between the hours of 1 P.M. and 5-30 P.M. on all office days.

2. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer's Office. The tenders should be accompanied by a statement in the form given below showing the rates at which different items specified will be executed.

3. Each tender must be accompanied by a deposit of Rs. 150 (one hundred and fifty) in cash on Government Promissory Notes, as earnest money and be superscribed "Tender for shifting the Galigekere village" at Krishnarajanagar in default of which tenders will be rejected.

4. The final acceptance of the tender will rest with the Executive Engineer, Krishnarajasagara Division, who does not bind himself to accept the lowest or any tenders or to assign any reason whatever for the rejection of any tender.

5. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

6. The name of the successful competitor whose tender has been accepted will be posted on the Notice Board of the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

7. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned on the production of printed receipts granted to them.

8. Rates once tendered will not be enhanced or altered on any account.

9. Rates for lampsum items non-tendered or non-estimated items shall be as per schedule rates of the department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

10. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Eangineer will be final and legally binding.

11. Quotations must be given in words as well as in figures and they must be in specific term of unit as shown againt each item of work.

12. Any quotation quoted at so much percentage less or more than the estimated rate or amount will not be accepted.

Abstract estimate of quantities of work required to be executed for shifting the Galigekere village, Krishnarajanagar Taluk.

No.	Items of work	Unit	Quantity	Tendered rate	
				In figures	In words
	I. FORMATION OF SITE.				
1	Earthwork excavation in gravelly soil and forming roads	C.yd.	749		
2	Providing and fixing site number stones ..	No.	80		
	II. APPROACH ROAD TO THE NEW VILLAGE.				
1	Excavating site drains and forming the roads	Lump-sum	..		
	III. CONSTRUCTING A SLABED CULVERT AND CAUSE WAYS.				
	(a) *Constructing a cause way* 60 *ft. long.*				
1	Earthwork Excavation	C.yd.	40		
2	New rough stone work with jelly backing ..	,,	40		
3	Burnt stone slabs 6″ thick dressed and fixed.	Sq.ft.	180		

No.	Items of work	Unit	Quantity	Tendered rate	
				In figures	In words
4	Stone jelly concrete in surki mortar ..	C.ft.	169		
5	Size stone in surki mortar ..	,,	155		
6	Providing cast iron pipes 9 ft. long and 12" dia.	Cwt.	26		
7	Conveying from Hampapur Railway Station and fixing the pipe	Lump-sum	..		
8	Unforeseen and baling water changes ..	,,	..		
	(b) *Constructing a slabed culvert across waste weir Halla of Hosagrahar Tank.*				
1	Earthwork excavation (foundation) ..	C.yd.	47		
2	Stone jelly concrete in surki mortar ..	C.ft.	871		
3	Size stone in surki mortar	,,	713		
4	Cut stone work dressed and put up ..	,,	135		
5	Burnt stone slabs 6" thick dressed and fixed.	Sq.ft.	108		
6	Raw stone slabs 9" dressed and fixed ..	,,	600		
7	Cement pointing	Sqr.	3·00		
8	Gravelling the road surface over the culvert and consolidation including ½ mile lead ..	C.yd.	10		
9	Collecting, spreading and consolidating with 4" size field metal	,,	10		
10	Providing stone uprights 2 ft. above foundation level placed at 4 ft. apart from centre to centre	Sq.ft.	105		
11	New rough stone work	C.yd.	22		
12	Earthwork to approaches	Lump-sum	..		
13	Watering foundations and unforseen charges.	,,			
14	Repairing the existing cart tracks ..	,,			
15	Burnt stone slabs to be released from waste weir of Galligekere Tank and fixed including carting to the site	Sq.ft.	300		
	(c) *Providing an additional cause way to dispose of surplus water.*				
1	Forming an approach to the cause way about 150 ft. lower down the culvert site ..	Lump-sum	..		
2	Rough stone work new	C.yd.	86		
	IV. SINKING A WELL 60 FT. DEEP.				
1	Excavating well in hard gravelley soil from 0 to 3 ft. depth	C.yd.	16		
	Do soft rock 3 to 6 do	,,	16		
	Do do 6 to 12 do	,,	32⅔		
	Do do 12 to 15 do	,,	16		
	Do hard rock 15 to 18 do	,,	108		
	Do do 18 to 21 do	,,	108		
	Do do 21x24 do	,,	108		
	Do do 24x57 do	,,	108		
	Do do 27x30 do	,,	108		
	Do do 30x33 do	,,	108		
	Do do 33x36 do	,,	108		
	Do do 36x39 do	,,	108		
	Do do 39x42 do	,,	108		
	Do do 42x45 do	,,	108		
	Do do 45x48 do	,,	108		
	Do do 48x51 do	,,	108		
	Do do 51x54 do	,,	108		
	Do do 54x57 do	,,	108		
	Do do 57x60 do	,,	108		

No.	Name of work	Unit	Quantity	Tender rate	
				In figures	In words
2	Stone jelly concrete in surki mortar ..	C.ft.	218		
3	Burnt stone slabs 6" thick dressed and fixed.	Sq.ft.	46		
4	Stone pillars 6" thick dressed and fixed ..	,,	55		
5	Rough stone steening work to well ..	C.yd.	34		
6	Jelly stone filling behind steening work ..	,,	23		
7	Size stone in surki mortar	C.ft.	188		
8	Pointing in surki mortar	Sqr.	3·50		
9	Making notches in beams, etc. ..	Lump sum			
10	Pulleys with iron rod	No.	2		
11	Bailing water	Lump sum			
12	Providing cattle trough near the well in stone	,,			

B. KRISHNASWAMIENGAR,
Executive Engineer.

IRWIN CANAL DIVISION.

Notification dated 12th December 1934.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Irwin Canal Division, up to 1 P.M., on 12th January 1935, for running telephone line from Hosur to Keragode. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of official year 1934-35.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mandya between the hours of 11 A.M. to 5 P.M. on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government Promissory Notes, as earnest money, and be superscribed " Tender for running Telephone Line from Hosur to Keragode " in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, Irwin Canal Division, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The rates are to be entered both in figures and words.

10. Rates once tendered will on no account be increased afterwards.

11. Tenders stating that the dues in the department may be adjusted towards the earnest money will be rejected.

Estimate of the probable cost of running Telephone Line from Hosur to Keragode on A.K.L. as per accompanying sketch to a distance of $4\frac{1}{2}$ miles.

Sl. No.	Name of materials	Unit	Quantity	Rate	Amount
					Rs. a. p.
1	S. M. Rail 24' long	No.	108		
2	X arm 2 pin D.C.A. with clamps, bolts and nuts, etc., complete	,,	18		
3	Do S. C. A. complete ..	,,	90		
4	Insulator white 2nd grade with pins, wooden, complete	,,	252		
5	Wire, galvanised, No. 8 S.W.G.	lbs.	3,500		